

TO: . . .  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-23205-00-00  
Spot: NENWNENE Sec/Twnshp/Rge: 1-9S-17W  
5000 feet from S Section Line, 985 feet from E Section Line  
Lease Name: HRABE A Well #: 3  
County: ROOKS Total Vertical Depth: 3345 feet

Operator License No.: 33263  
Op Name: BOWMAN, WILLIAM F. DBA THE BILL  
Address: 2640 WRD  
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3340		240 SX
SURF	8.625	216		135 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/02/2015 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DONALD A. BOWMAN Company: THE BILL BOWMAN OIL CO. Phone: (785) 885-4830

Proposed Plugging Method: Ordered 340 sx 60/40 pozmix 4% gel cement w/300 # hulls.  
DV Tool at 1232' w/240 sx cement  
Production perforations: 3042' - 3300'  
Bottom sanded off to 2905' per operator

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/02/2015 11:10 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2825' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 1457' and pumped 150 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing. Put swedge on 5 1/2" casing and pumped 15 sx cement. Shut in pressure 450 psi. Hooked to 8 5/8" x 5 1/2" annulus and pressured to 200 psi immediately.

GPS: 39.30626N -099.16138W

Perfs:

Top	Bot	Thru	Comments
3276			
3267			
3239			
3220			
3175			
3164			
3156			
3131			
3122			
3063	3300		
3042	3052		

Remarks: ALLIED TICKET # 55716

Plugged through: TBG

OCT 09 2015  
CKM

District: 04

Signed \_\_\_\_\_

Pat Bedore

KCC WICHITA (TECHNICIAN)

(M)

SEP 03 2015

SEP 29 2015

RECEIVED