

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-21160-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 7-29S-6W  
1650 feet from N Section Line, 1650 feet from E Section Line  
Lease Name: MINNIE BENSON Well #: 1  
County: KINGMAN Total Vertical Depth: 4542 feet

Operator License No.: 5348  
Op Name: CAMPBELL, ROBERT E.  
Address: 260 N ROCK RD STE 110  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4541		175 SX
SURF	8.625	234		225 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/16/2015 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (316) 685-6001

Proposed Plugging Method: Per KCC Regulations

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/16/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

RAN TUBING INTO 4062' SPOTTED 25 SX CEMENT, TAGGED TOC @ 3830. CUT CASING PIPE OFF @ 2465' PULLED CASING TO 1046' SPOTTED 35 SX CEMENT. PULLED CASING TO 584' SPOTTED 35 SX CEMENT. PULLED CASING TO 287' CIRCUALTED TO SURFACE WITH 145 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4135	4139		
4133	4136		

Remarks: CLASS A CEMENT PROVIDED BY QUAILTY WELL SERVICE. TEN YEAR TA PAST.

Plugged through: CSG

OCT 09 2015  
CKM

District: 02

Signed

(TECHNICIAN)  
KCC WICHITA

SEP 28 2015

RECEIVED

Form CP-2/3

JK