

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-20866-00-00
Spot: NWNE5W Sec/Twnshp/Rge: 9-29S-6W
2010 feet from S Section Line, 3562 feet from E Section Line
Lease Name: KLAVER Well #: 4
County: KINGMAN Total Vertical Depth: 4472 feet

Operator License No.: 5348
Op Name: CAMPBELL, ROBERT E.
Address: 260 N ROCK RD STE 110
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4470		350 SX
SURF	8.625	246		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2015 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (316) 685-6001

Proposed Plugging Method: Per KCC Regulations

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/14/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP @ 2975, CAPPED WITH 2" 2 SX CEMENT ON TOP. TRIPPED TUBING INTO 2900' SPOTTED 30 SX CEMENT, TAGGED TOP OF CEMENT @ 2750'. CUT CASING PIPE OFF @ 1902' PULLED CASING TO 1152' SPOTTED 35 SX CEMENT. PULLED CASING TO 520' SPOTTED 35 SX CEMENT. PULLED CASING TO 300' CIRCULATED TO SURFACE WITH 120 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4461	4465		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB ALSO, ALL CLASS A CEMENT. PAST 10 YEAR TA.

Plugged through: CSG

OCT 09 2015 *CKM*

District: 02

Signed B. J. Hope

KCC WICHITA
(TECHNICIAN)

SEP 26 2015

RECEIVED

✓