

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-081-20084-00-00  
Spot: NW Sec/Twnshp/Rge: 12-29S-32W  
3921 feet from S Section Line, 2995 feet from E Section Line  
Lease Name: HULL Well #: 1-12  
County: HASKELL Total Vertical Depth: 2725 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2725	0	WITH 550 SX CMT
SURF	8.625	667		WITH 500 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/15/2015 1:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FINCH Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 200# HULLS & 120 SX CMT. DISPLACE TO 800'. TEST TO 500 PSI. RUN CBL FROM 800' TO 0'. IF CMT IS UP TO 450', RUN TBG TO 700' & FILL 4 1/2" CASING WITH CMT. PUMP CMT DOWN ANNULUS. IF CMT IS BELOW 500'. PERFORATE THE 4 1/2" RUN TBG TO 700' & CIRCULATE CMT UP 4 1/2" & 4 1/2" X 8 5/8" ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/15/2015 5:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

PUMP 200# HULLS & 120 SX CMT. DISPLACE WITH 14 BBLS. HELD AT 500#. TOC APPROXIMATELY @ 864'. PERFORATE AT 675'. RUN TBG TO 700'. CIRCULATE 100 SX CMT. PUMP 50 SX CMT DOWN BACKSIDE TO 200#. TOP OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2680	2690		

OCT 09 2015  
CKM

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
SEP 21 2015  
KCC DODGE CITY

JVA  
KCC WICHITA  
OCT 02 2015  
RECEIVED