

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21659-01-00
Spot: W2SWSW Sec/Twnshp/Rge: 6-29S-20W
610 feet from S Section Line, 158 feet from W Section Line
Lease Name: RUDD Well #: I-H
County: KIOWA Total Vertical Depth: 5114 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3760		WITH 4 SX CMT
CIBP		5612		WITH 50 SX CMT
CIBP	5.5	6048		
L1	5.5	8046	3792	WITH 90 SX CMT
PROD	7.625	5730	2304	WITH 300 SX CMT
SURF	10.75	814		WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/11/2015 4:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 5622' WITH 50 SX CMT. PLUG AT 1400' WITH 20 SX GEL & 100 SX CMT. PLUG AT 850' WITH 80 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 09/11/2015 6:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5612' WITH 50 SX CMT. COULD NOT LOAD 7 5/8" CASING. SET CIBP @ 3760' WITH 4 SX CMT. CUT & PULLED CASING AT 2304'. 1ST PLUG AT 1411' WITH 20 SX GEL & 100 SX CMT. 2ND PLUG AT 855' WITH 80 SX CMT. 3RD PLUG AT 362' WITH 50 SX CMT. 4TH PLUG AT 61' WITH 55 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8046	9000		
5672	5910		

KCC WICHITA

SEP 28 2015

RECEIVED

OCT 09 2015
CKM


Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED. TMD = 9000'.

Plugged through: TBG

District: 01

RECEIVED
SEP 21 2015
KCC DODGE CITY

Signed


SA
(TECHNICIAN)