

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-22092-00-00  
Spot: NENESW Sec/Twnshp/Rge: 5-17S-26W  
2263 feet from S Section Line, 3022 feet from E Section Line  
Lease Name: BOWER Well #: 2  
County: NESS Total Vertical Depth: 4606 feet

Operator License No.: 5135  
Op Name: FARMER, JOHN O., INC.  
Address: 370 W WICHITA AVE PO BOX 352  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4605	0	WITH 335 SX CMT
SURF	8.625	262		WITH 170 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/16/2015 9:00 AM  
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.  
Proposal Rcvd. from: VAL DREHER Company: FARMER, JOHN O., INC. Phone: (785) 483-3145

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 200# HULLS. PERFORATE AT ANHYDRITE & SPOT 50 SX CMT. PERFORATE AT PERMIAN & PUMP 80 SX CMT OVER CASING VOLUME. IF DOESN'T CIRCULATE PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/17/2015 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

TRIED TO GET TO BOTTOM FOR 2 DAYS WITH BIT & SCRAPER, COULDN'T GET BELOW 1730'. RUN TBG TO 1700' & SPOTTED 50 SX 60/40 POZMIX 4% GEL 3% CC CMT & 400# HULLS. PULLED TBG TO 1000' & WAITED 1 HOUR. RUN BACK IN TO TAG DIDN'T HIT ANY CMT. PULLED TBG TO 1500' & SPOTTED 50 SX 60/40 POZMIX 4% GEL 3% CC & 200# HULLS. PULLED TBG TO 800'. WAIT 1 1/2 HOURS. PUMPED 80 SX 60/40 POZMIX 4% GEL & 200# HULLS. WENT ON VACUUM. SDON. 9/17/15: RUN TBG TO 1500' NO CMT. PUMPED 50 SX 60/40 POZMIX 4% GEL 4% CC. GOT CIRCULATION. PULLED TBG TO 700'. WAITED 1 HOUR. PRESSURE CASING TO 300# & HELD. FOUND CMT AT 680'. PERFORATED AT 650' WITH 4 SHOTS, COULDN'T PUMP INTO IT AT 1000#. RUN TBG TO 630' & PUMP 50 SX CMT. CIRCULATED TO PIT. TIED ONTO CASING & PUMPED 10 SX CMT. PRESSURED TO 1000# & HELD. TIED ONTO BACKSIDE & PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4495	4487		
4213	4210		
4192	4188		
4182	4180		
4172	4168		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS & HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY QUALITY CEMENTING.

Plugged through: TBG

OCT 09 2015  
CKM

District: 01

RECEIVED  
SEP 22 2015  
KCC DODGE CITY

Signed Michael J. Maier  
(TECHNICIAN)  
KCC WICHITA

SEP 28 2015  
RECEIVED