

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26686-00-00
Spot: NESWNESE Sec/Twnshp/Rge: 27-13S-19W
1705 feet from S Section Line, 810 feet from E Section Line
Lease Name: SACK Well #: 1
County: ELLIS Total Vertical Depth: 3795 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3793		150 SX
SURF	8.625	218		150 SX
T1	2.875	3717		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/28/2015 1:30 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: TERRY PIESKER Company: HESS OIL CO. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement, 12 sx gel and 500 # hulls.
Perforations: 3549' - 3596' LKC
PC at 1351' w/200 sx cement

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/28/2015 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality rigged to 5 1/2" casing and mixed and pumped 50 sx cement w/300 # hulls, followed by 12 sx gel, followed by 200 sx cement w/200 # hulls mixed in. Pumped to pressure with 600 psi. Shut in pressure 500 psi. Rigged to 8 5/8" surface casing and pumped 10 sx cement to pressure.

GPS: 38.89004 -099.41320

Perfs:

Top	Bot	Thru	Comments
3549	3596		


Remarks: QUALITY OILWELL CEMENTING CO. TICKET # 1030

Plugged through: CSG

OCT 09 2015
CKM

District: 04

Signed _____



(TECHNICIAN)

CM

KCC WICHITA

SEP 29 2015

RECEIVED

SEP 03 2015

Form CP-2/3