

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-24994-00-00  
Spot: SWNENENW Sec/Twnshp/Rge: 9-33S-14E  
4676 feet from S Section Line, 3120 feet from E Section Line  
Lease Name: IDA MAE WRIGHT EAST Well #: 8  
County: MONTGOMERY Total Vertical Depth: 1250 feet

Operator License No.: 32255  
Op Name: KANSAS ENERGY COMPANY, L.L.C.  
Address: BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	1200		0 SX
SURF	7	20		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/16/2015 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: P.J. BUCK Company: \_\_\_\_\_ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/17/2015 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1150' gelled hole and spotted 2 sack plug. Pulled up to 700' and spotted 2 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. Ran 1" to 80' on backside of well and circulated 8 sacks of cement to surface. A total of 24 sacks of cement were used to plug this well.

Perfs:

RECEIVED  
KCC DIST # 3  
SEP 29 2015  
CHANUTE, KS

DS


Remarks:

Plugged through: TBG

OCT 09 2015

District: 03

Signed



(TECHNICIAN)

KCC WICHITA

Form CP-2/3

OCT 02 2015

RECEIVED