

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

March 6, 1982

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Gib Overby of Mustang Drilling + Exploration has this date requested permission to plug the following described well:

Operator's Full Name: Petromark Exploration, Inc

Complete Address: Copper Oaks Office Bldg., 7030 South Gale, Tulsa, Oklahoma 74177

Lease Name: Lyon Well No. 1

Location: SE NW NW Sec. 17 Twp. 25 Rge. 13 (E) (W)

County: Stafford Total Depth: 4326

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Overby was instructed to plug the well as follows:

8 5/8" - 408' set @ 415' w/ 325 sacks Common 2% gel 3% c.c. Anhydrite 827' (Top)
Circulate hole and fill with mud. Pump 60 sacks cement through
drill pipe at 600'. Pump 40 sacks cement through drill pipe at
400'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls
to 40' and cap hole with 10 sacks cement. Cement rat hole
with 10 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent