

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 16 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. A. B. Kelley of Rock Island Oil & Ref. Co has this
 date requested permission to plug the following described well:

Mr. Kelley guarantees payment of the plugging fee.

Operator's full Name: Rock Island Oil & Refining Co., Inc.

Complete Address: 321 W. Douglas, Wichita, Kansas

Lease Name: Garner Well No. # 1

Location: SW SW SE Sec. 17 Twp. 25 Rge. 13 (E) (W) W

County Stafford Total Depth 4385 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kelley was instructed to plug the well as follows:

370' of 10 3/4" surface pipe, cemented with 275 sacks.
Fill hole with drilling mud to 275', 1st cementing plug,
bridge with hulls, cement with 30 sacks. Fill hole with
drilling mud to 40', 2nd cementing plug, bridge with hulls,
cement with 15 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent