

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-22299-00-00
Spot: NWSWNESE Sec/Twnshp/Rge: 22-16S-12W
1972 feet from S Section Line, 995 feet from E Section Line
Lease Name: RIEMANN A Well #: 1
County: BARTON Total Vertical Depth: 3400 feet

Operator License No.: 9951
Op Name: KRIER, KIRBY OIL, INC.
Address: 1043 NE 80TH RD
CLAFLIN, KS 67525

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3398 | | 110 SX |
| SURF | 8.625 | 365 | | 225 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/22/2015 8:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: KIRBY KRIER Company: KRIER OIL Phone: (620) 562-7637

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 500 # hulls and 10 sx gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2015 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 780' and 300'. Ran tubing to 2900' and pumped 10 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1450' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 900' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 450'. Circulated cement to surface w/140 sx cement and 100 # hulls. Pulled tubing. Topped off casing with 10 sx cement at 250 psi. Tied to surface pipe and topped off with 10 sx cement at 200 psi.

GPS: 38.643017 -098.63046

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3398 | 3400 | | |

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

OCT 09 2015
CKM

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

KCC WICHITA

SEP 29 2015

RECEIVED

SEP 23 2015