

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21727-00-00
Spot: SESWSWSW Sec/Twnshp/Rge: 8-27S-20W
202 feet from S Section Line, 4628 feet from E Section Line
Lease Name: EINSEL Well #: 1 SWD
County: KIOWA Total Vertical Depth: 6190 feet

Operator License No.: 34320
Op Name: LASSO ENERGY LLC
Address: PO BOX 465
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4300		WITH 15 SX CMT
CIBP		5530		
PROD	7	5570	0	WITH 175 SX CMT
SURF	9.625	990		WITH 400 SX CMT

Well Type: SWD UIC Docket No: D31277.0 Date/Time to Plug: 09/11/2015 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MATT BURTON Company: LASSO ENERGY Phone: (620) 259-4000

Proposed Plugging Method: SET CIBP @ 4315' WITH 5 SX CMT. PERFORATE AT 1040' & CIRCULATE TO SURFACE.

Plugging Proposal Received By: WADE KLAUS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/11/2015 10:45 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4300' WITH 15 SX CMT. PERFORATE AT 1040' & PUMPED 180 SX CMT, CIRCULATING INSIDE THE 7". CLOSED THE 7" & CONTINUED PUMPING UP THE 9 5/8" BUT PRESSURED UP. TIED ONTO THE 9 5/8" CASING & CIRCULATED BACK THROUGH THE TBG WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5570	6190		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

OCT 09 2015
CKM

District: 01

RECEIVED
SEP 24 2015
KCC DODGE CITY

Signed [Signature]
SA (TECHNICIAN)
KCC WICHITA
SEP 28 2015
RECEIVED

UIC ✓
Form CP-2/3