

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21729-01-00
Spot: S2S2SWSW Sec/Twnshp/Rge: 8-27S-20W
195 feet from S Section Line, 4597 feet from E Section Line
Lease Name: EINSEL Well #: 1-8H
County: KIOWA Total Vertical Depth: 4873 feet

Operator License No.: 34320
Op Name: LASSO ENERGY LLC
Address: PO BOX 465
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5110		
COND	20	80		WITH 425 SX CMT
L1	4.5	9578	0	WITH 450 SX CMT
PROD	7	5473	0	WITH 200 SX CMT
SURF	9.625	895		WITH 350 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/11/2015 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MATT BURTON Company: LASSO ENERGY Phone: (620) 259-4000

Proposed Plugging Method: CIBP @ 5110' WITH 50 SX CMT. PLUG AT 1320' WITH 50 SX CMT. PERFORATE AT 950' & CIRCULATE CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/11/2015 3:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5110' WITH 50 SX CMT ON TOP. 1ST PLUG AT 1340' WITH 30 SX CMT.
PERFORATED AT 950' & CIRCULATED CMT TO SURFACE WITH 220 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5580	9510		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY. TMD = 9578'

Plugged through: CSG

OCT 09 2015
CKM

District: 01

Signed



RECEIVED
SEP 24 2015
KCC DODGE CITY

KCC WICHITA
SEP 28 2015
RECEIVED