

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-03197-00-00
Spot: W2NENWNW Sec/Twnshp/Rge: 13-15S-18W
4990 feet from S Section Line, 4340 feet from E Section Line
Lease Name: LEIKER TS Well #: 7
County: ELLIS Total Vertical Depth: 3599 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3598 | | 150 SX |
| SURF | 8.625 | 1164 | | 550 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/09/2015 12:30 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: KENT WILLSON Company: MAI OIL OPERATIONS Phone: (785) 483-1663

Proposed Plugging Method: 09/09/2015- Ordered 75 sx of hot (Class A w/3% cc) cement.
09/10/2015- Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls and 10 sx gel

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/10/2015 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

09/09/2015- Ran tubing to 3535' and pumped 75 sx hot cement. Displaced tubing. POOH.
09/10/2015- Wire line truck tagged TOC at 3030', pulled up and perforated at 1400' and 1150'.
Ran tubing to 2697' and pumped 9 sx gel. Pulled tubing to 1800' and pumped 100 sx cement.
Pulled tubing to 800' and pumped 100 sx cement. Cement circulated out backside and fluid out of the braden head. POOH. Hooked to casing pumped 130 sx cement and circulated out the braden head.

GPS: 38.75420 -099.27930

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3476 | 3486 | | |
| 3456 | 3462 | | |
| 3432 | 3442 | | |
| 3322 | 3328 | | |
| 3273 | 3278 | | |

Remarks: QUALITY CEMENTING TICKET # 1489 AND 1036

Plugged through: TBG

OCT 09 2015
CYM

District: 04

Signed Ray Dinkel
(TECHNICIAN)

KCC WICHITA

CM

SEP 29 2015

RECEIVED

Form CP-2/3

SEP 17 2015