

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-23303-00-00
Spot: W2E2SE Sec/Twnshp/Rge: 15-12S-15W
1220 feet from S Section Line, 1090 feet from E Section Line
Lease Name: HABERER Well #: 1-15
County: RUSSELL Total Vertical Depth: 3299 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3299	1826	135 SX
SURF	8.625	803		375 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/15/2015 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BRENT HOMEIER Company: MAI OIL OPERATIONS Phone: (785) 938-2943

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Cut casing at 1826' leaving 1430' of 5 1/2" casing in the hole.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2015 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

09/14/2015- Sanded off the bottom to 2800' and spotted 5 sx cement. Cut casing at 1826'.
09/15/2015- Pulled casing to 1450' and pumped 125 sx cement w/300 # hulls. Pulled casing to 800' and pumped 40 sx cement w/50 # hulls. Pulled casing to 350' and pumped 70 sx cement. Cement circulated to pit. POOH. Cellar stayed full.

GPS: 39.00511 -098.96841

Perfs:

Top	Bot	Thru	Comments
3194	3196		
3188	3192		
3182	3184		
3056	3060		
2934	2940		
2920	2924		
2902	2906		

Remarks: QUALITY CEMENTING TICKET # 1626

Plugged through: CSG

OCT 09 2015
CKM

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

KCC WICHITA

CM

SEP 29 2015

RECEIVED

Form CP-2/3

SEP 17 2015