

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-23364-00-00
Spot: SWNESW Sec/Twnshp/Rge: 28-15S-11W
1710 feet from S Section Line, 1780 feet from W Section Line
Lease Name: SWART Well #: 1
County: RUSSELL Total Vertical Depth: 3300 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3293	2300	135 SX
SURF	8.625	398		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2015 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BRENT HOMEIER Company: MAI OIL OPERATIONS Phone: (785) 445-2353

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/10/2015 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

09/09/2015- Sanded back to 2800' and spotted 5 sx cement on top.
09/10/2015- Cut pipe at 2300'. Pulled to 1200' and pumped 125 sx cement w/300 # hulls.
Pulled casing to 620' and pumped 40 sx cement w/50 # hulls. Pulled casing to 350' and pumped 65 sx cement to circulate cement to cellar. POOH. Cellar stayed full.

GPS: 38.71607 -098.55379

Perfs:

Top	Bot	Thru	Comments
3110	3114		
3068	3072		
2930	2934		
2899	2903		

Remarks: QUALITY CEMENTING TICKET # 3725

Plugged through: CSG

OCT 09 2015
CJM

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CJM

KCC WICHITA

SEP 29 2015

RECEIVED

SEP 17 2015

Form CP-2/3