

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-01758-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 23-10S-21W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: PIERCE Well #: 1
County: GRAHAM Total Vertical Depth: 3737 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3735		125 SX
SURF	8.625	267		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/18/2015 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL, INC. Phone: (620) 938-2943

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/18/2015 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3597' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 2100' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 600' and pumped 50 sx cement. Circulated cement to pit. POOH. Hooked to casing and pumped 20 sx cement at 500 psi. Shut in. Hooked to braden head and pumped 15 sx cement at 200 psi.

GPS: 39.17540 -099.63202

Perfs:

Top	Bot	Thru	Comments
3618	3624		
3558	3564		
3500	3508		
3424	3429		

Remarks: COPELAND CEMENTING AND ACID COMPANY TICKET # 423

Plugged through: TBG

OCT 09 2015
CKM

District: 04

Signed

Ray Dinkel

KCC WICHITA (TECHNICIAN)

CM

SEP 22 2015

SEP 29 2015

Form CP-2/3

RECEIVED