

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-039-21018-00-00
Spot: SESWNWSE Sec/Twnshp/Rge: 7-5S-29W
1420 feet from S Section Line, 2280 feet from E Section Line
Lease Name: FREDRICKSON Well #: 7-1
County: DECATUR Total Vertical Depth: 4405 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4142		180 SX
SURF	8.625	237		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/09/2015 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 269-7290

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls.
8 5/8" surface casing set at 237' w/160 sx cement.
4 1/2" production casing set at 4142' w/180 sx cement.
TD 4405', PBTD 4102'.
Perforations: 4079' - 4083', 4052' - 4055', 3986' - 3988', 3973' - 3977', 3945' - 3948', 3934' - 3936', 3906' - 3908', 3892' - 3896' and 3752' - 3844'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/09/2015 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 2575' and 1865'. Ran tubing to 3748' and pumped 100 sx cement w/400 # hulls. Pulled tubing to 2778' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1388' and pumped 100 sx cement w/100 # hulls. CWC. Pulled tubing to surface. Connected to 4 1/2" casing and pumped 20 sx cement. Connected to 8 5/8" surface casing and pumped 55 sx cement.

GPS: 39.62987N -100.61823W

Perfs:

Top	Bot	Thru	Comments
4079	4083		
4052	4055		
3986	3988		
3973	3977		
3945	3948		
3934	3936		
3906	3908		
3892	3896		
3752	3844		

Remarks: SWIFT SERVICES TICKET # 27,166

Plugged through: TBG

OCT 09 2015
CXM

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

KCC WICHITA

SEP 29 2015

RECEIVED

Form CP-2/3

SEP 11 2015