

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-21392-00-00
Spot: SENWNWNW Sec/Twnshp/Rge: 34-33S-29W
335 feet from N Section Line, 335 feet from W Section Line
Lease Name: STOLTZFUS Well #: 1-34
County: MEADE Total Vertical Depth: 6460 feet

Operator License No.: 32211 String Size SURF 8.625 Depth (ft) 1496 Pulled (ft) Comments WITH 500 SX CMT
Op Name: O'BRIEN ENERGY RESOURCES CORP.
Address: 18 CONGRESS ST, STE 207
PORTSMOUTH, NH 03801

Well Type: DH UIC Docket No: Date/Time to Plug: 09/03/2015 2:15 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: ROGER PEARSON Company: O'BRIEN ENERGY RESOURCES Phone: (603) 427-2099

Proposed Plugging Method: 1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 80 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 09/03/2015 6:45 AM KCC Agent: KEN JEHLIK

Actual Plugging Report: Perfs:

1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 80 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

KCC WICHITA
SEP 28 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY NOVA SERVICES.

Plugged through: DP

District: 01

Signed *Ken Jehlik* **OCT 09 2015**
SA (TECHNICIAN) *CKM*

RECEIVED
SEP 17 2015
KCC DODGE CITY *MP*