

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-00992-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 27-29S-7W  
1650 feet from S Section Line, 990 feet from E Section Line  
Lease Name: VORAN C Well #: 2  
County: KINGMAN Total Vertical Depth: 4180 feet

Operator License No.: 32215  
Op Name: RAKESTRAW BROS., L.L.C  
Address: 4566 NE PARALLEL RD  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4158		
SURF	8	405		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/08/2005 12:00 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: KURT RAKESTRAW Company: RAKESTRAW BROTHERS Phone: \_\_\_\_\_

Proposed Plugging Method: CIBP 50 SXS 1150' (MAYBE SQUEEZED) 50 SXS @ 700'. CIRCULATE 450'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/08/2005 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP AT 4100' & CAPPED WITH 2 SKS CEMENT. PERFORATED CASING AT 1150'. TIED ON TO CASING AND PUMPED WATER. WELL PRESSURED UP. WELL SQUEEZED AT 1150'. PERFORATED CASING AT 700'. TIED ONTO CASING & SQUEEZED 50 SX, LEAVING 50' OF CEMENT INSIDE PIPE. PERFORATED CASING AT 450' & CIRCUALTED CEMENT TO SURFACE USING 300 SXS CEMENT.

Perfs:


Top	Bot	Thru	Comments
4158	4180	OH	

Remarks: ALLIED CEMENT 60/40 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

OCT 09 2015

CKM

Received  
KANSAS CORPORATION COMMISSION

OCT 09 2015

CONSERVATION DIVISION  
WICHITA, KS

