

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-21926-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 22-18S-9W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: CONNOR Well #: 1
County: RICE Total Vertical Depth: 3307 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3307		135 SX
SURF	8.625	200		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/18/2015 10:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: ROBIN AUSTIN Company: RAMA OPERATING CO. Phone: (620) 234-5191

Proposed Plugging Method: PER KCC RULES & REGS. OPERATOR WAS SENT THE TA - N.O.V. LETTER BUT NEVER FILED CP-111.

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 09/18/2015 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3197' AND CAP WITH 5 SX'S CEMENT. PERFORATE AT 1175', 825', AND 250'. RUN TUBING TO 1175' AND PUMP 35 SX'S CEMENT WITH 2% CC AND PULL UP TO 825'. LET SET AWHILE AND TAG CEMENT AT 1000'. PUMPED 35 SX'S AT 825', PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE OUT OF BOTH CASINGS. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3247	3250	CSG	

Remarks: LOG TECH OF KS #8580. BASIC SERVICES #12713A.

Plugged through: TBG

OCT 09 2015
CKM

District: 02

Signed Virgil Clothier
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 01 2015

CONSERVATION DIVISION
WICHITA, KS

JK