

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-21150-00-00  
Spot: SWNWSW Sec/Twnshp/Rgc: 20-34S-2E  
1650 feet from S Section Line, 330 feet from W Section Line  
Lease Name: CULLY Well #: 4-20  
County: SUMNER Total Vertical Depth: 3200 feet

Operator License No.: 32705  
Op Name: RANEY OIL COMPANY, LLC  
Address: 4665 BAUER BROOK CT.  
LAWRENCE, KS 66049

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3249		225 SX
SURF	8.625	179		179 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/04/2015 12:00 AM  
Plug Co. License No.: 34879 Plug Co. Name: CANAAN WELL SERVICE INC.  
Proposal Rcvd. from: CANAAN WELL SERVICE I Company: CANAAN WELL SERVICE Phone: (620) 440-0170

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/05/2015 12:00 AM KCC Agent: DAN FOX

**Actual Plugging Report:**

RAN IN WITH TUBING AND FOUND TD TO BE AT 3200' SANDED OFF BOTTOM TO 2890', DUMPED 2 SX OF CEMENT ON TOP OF SAND. RAN BACK IN WITH TUBING AND SPOTTED 35 SX OF CLASS A CEMENT AND 2% CC @ 1600'. AFTER A COUPLE OF HOURS WENT BACK IN AND TAGGED TOP OF CEMENT @ 1276'. WELL-BORE STAYED LOADED. AND THEN SHOT 4 HOLES AT 300', CIRCULATE CEMENT TO SURFACE WITH AN ADDITIONAL 115 SX. PLUG JOB COMPELTE.

**Perfs:**

Top	Bot	Thru	Comments
3192	3198	TBG	

Remarks: THIS WELL PLUGGED AS RESULT OF COMMISSION ORDER 16-CONS-145-CPEN

Plugged through: TBG

District: 02

Signed

*Daniel F. Fox*  
(TECHNICIAN)

OCT 09 2015  
CKM

KCC WICHITA

Form CP-2/3

OCT 07 2015

RECEIVED

*JK*