

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-20237-00-01  
Spot: SE Sec/Twnshp/Rge: 5-31S-11W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: CARGILL Well #: 2  
County: BARBER Total Vertical Depth: 4460 feet

Operator License No.: 5046  
Op Name: RAYMOND OIL COMPANY, INC.  
Address: PO BOX 48788  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3650		WITH 2 SX CMT
CIBP		3780		
PROD 4.5		3850	1976	WITH 150 SX CMT
SURF 8.625		307		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/23/2015 8:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 3650' & 2 SX CMT. PLUG AT 650' WITH 15 SX GEL & 50 SX CMT. PLUG AT 325' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: NONE  
Date/Time Plugging Completed: 09/23/2015 4:15 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 3650' & 2 SX CMT. 1ST PLUG AT 660' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 321' WITH 50 SX CMT. 3RD PLUG AT 63' WITH 70 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3704	3714		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

  
(TECHNICIAN)

KCC WICHITA

OCT 02 2015

RECEIVED

OCT 09 2015 CKM

RECEIVED  
SEP 25 2015  
KCC DODGE CITY 