

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-057-20585-00-01  
Spot: W2SWSE Sec/Twnshp/Rge: 2-26S-22W  
661 feet from S Section Line, 2162 feet from E Section Line  
Lease Name: PEINTNER TRUST Well #: 1  
County: FORD Total Vertical Depth: 4961 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4830		
PC		1440		WITH 350 SX CMT
PROD 4.5		4959	0	WITH 275 SX CMT
SURF 8.625		310		WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/15/2015 1:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 214-0300

Proposed Plugging Method: PUMP 30 SX CMT WITH 200# HULLS. SPACER TO 1500' CMT TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/15/2015 2:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 30 SX CMT WITH 200# HULLS FOLLOWED BY MUD SPACER THEN 75 SX CMT TO SURFACE. PRESSURED TO 800#. PRESSURED BACKSIDE TO 200# WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4858	4863		
4650	4660		
4429	4435		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

OCT 09 2015  
CKM

District: 01

Signed [Signature]

RECEIVED  
SEP 24 2015  
KCC DODGE CITY [Signature]

SA

(TECHNICIAN)  
KCC WICHITA

SEP 28 2015

RECEIVED