

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-057-20619-00-01
Spot: N2N2N2 Sec/Twnshp/Rge: 11-26S-22W
159 feet from N Section Line, 2641 feet from E Section Line
Lease Name: MORRIS-DROSTE Well #: 1
County: FORD Total Vertical Depth: 4928 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PC | | 1406 | | WITH 230 SX CMT |
| PROD | 4.5 | 4928 | 0 | WITH 225 SX CMT |
| SURF | 8.625 | 214 | | WITH 250 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/15/2015 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 214-0300

Proposed Plugging Method: PUMP 30 SX CMT WITH 200# HULLS. MUD SPACER TO 1500' CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2015 10:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 30 SX CMT WITH 200# HULLS FOLLOWED BY 48 BBL MUD SPACER TO 1500' THEN 90 SX CMT. PRESSURED TO 500#. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 200#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4686 | 4690 | | |
| 4570 | 4571 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

OCT 09 2015
CKM

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
SEP 24 2015
KCC DODGE CITY