

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-057-20792-00-00
Spot: NESW Sec/Twnshp/Rge: 2-26S-22W
1989 feet from S Section Line, 3003 feet from E Section Line
Lease Name: PEINTNER 2C Well #: 1
County: FORD Total Vertical Depth: 4960 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1434		CEMENTED WITH 195 SX CMT. 15 SX CMT CIRCULATED TO PIT.
PROD	4.5	4957	0	WITH 200 SX CMT
SURF	8.625	337		WITH 230 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/15/2015 11:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (316) 691-9500

Proposed
Plugging
Method:

PUMP 50 SX CMT WITH 200# HULLS, MUD SPACER TO 1500', CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2015 12:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 50 SX CMT WITH 200# HULLS, FOLLOWED BY A MUD SPACER TO 1500'
THEN 80 SX CMT TO SURFACE. PRESSURED TO 800#. PRESSURED THE BACKSIDE
TO 200# WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4661	4671		
4660	4670		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

OCT 09 2015
CKM

District: 01

Signed



(TELEPHONE)
KCC WICHITA

RECEIVED
SEP 24 2015
KCC DODGE CITY

SA

SEP 28 2015

RECEIVED