

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22587-00-00
Spot: E2E2SWSW Sec/Twnshp/Rge: 23-31S-1W
660 feet from S Section Line, 1275 feet from W Section Line
Lease Name: VAN ALLEN Well #: 1
County: SUMNER Total Vertical Depth: 4098 feet

Operator License No.: 34633
Op Name: SOURCE ENERGY MIDCON LLC
Address: 1805 SHEA CENTER DR., STE 100
HIGHLANDS RANCH, CO 80129

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3210		
PROD	5.5	3749	1900	195 SX
SURF	8.625	264		175 SX
T1	2.875	3192		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/18/2011 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: ROB BURKHART Company: SOURCE ENERGY Phone: (620) 218-0329

Proposed Plugging Method: CIBP SET @ 3600' & 2 SKS CEMENT. CIBP @ 3100' & 2 SKS CEMENT. CIRCULATE CEMENT FROM 359' - 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/29/2015 12:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE MISS PERFS WERE COVERED WITH CIBP TO 3600' & CAPPED WITH 2 SKS CEMENT. THE KC PERFS COVERED WITH A CIBP TO 3100' AND CAPPED WITH 2 SKS CEMENT. THE CASING WAS RECOVERED FROM 1900' & PULLED TO 350' WHERE CEMENT WAS CIRUCLATED TO SURFACE WITH 225 SXS.

Perfs:

Top	Bot	Thru	Comments
3667	3664	CSG	
3664	3667	CSG	MISSISSIPPI
3182	3168	CSG	
3176	3182	CSG	KANSAS CITY
3168	3173	CSG	KANSAS CITY

Remarks: QUALITY WELL SERVICE, COMMON CEMENT - DENIED TA

Plugged through: CSG

OCT 09 2015
ckm

District: 02

Signed _____

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

OCT 09 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

✓ SK