

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-22659-00-00  
Spot: SWNENWNW Sec/Twnshp/Rge: 6-30S-2W  
380 feet from N Section Line, 930 feet from W Section Line  
Lease Name: PAULY 3002 Well #: 6-1  
County: SUMNER Total Vertical Depth: 5121 feet

Operator License No.: 35053  
Op Name: TAPSTONE ENERGY, LLC  
Address: PO BOX 1608  
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	18	60		36 sx cement
H	8.75	4350		1000 sx cement
PROD	7	4350	1015	1120 SX
SURF	9.625	181		145 SX
T1	4.5	4291		

Well Type: SWD UIC Docket No: D31329.0 Date/Time to Plug: 09/17/2015 12:00 AM  
Plug Co. License No.: 35086 Plug Co. Name: SJL WELL SERVICE, LLC  
Proposal Rcvd. from: BOONE DAVIDSON Company: TAPSTONE ENERGY Phone: (620) 840-2367

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/17/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP WAS SET BY PREVIOUS OPERATOR @ 4200' WITH 100' OF CEMENT, TRIPPED TUBING IN TO VERIFY TOPS, TAGGED @ 4182', LOADED HOLE WITH MUD. CUT CASING PIPE OFF @ 1015' PULLED CASING. TRIPPED TUBING TO 500' SPOTTED 50 SX CEMENT. PULLED TUBING TO 250' CIRCULATED TO SURFACE WITH 90 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4350	5121		

Remarks: CLASSA CEMENT PROVIDED BY HURRICANE SERVICES, INC. OUT OF GARNETT KS. DENIED TA.

Plugged through: TBG

District: 02

Signed



KCC WICHITA

(TECHNICIAN) SEP 28 2015

RECEIVED

Form CP-2/3

OCT 09 2015 *CKM*

*UIC*

*JK*