

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22660-01-00

Spot: SWNENWNW

Sec/Twnshp/Rge: 6-30S-2W

380 feet from N Section Line,

940 feet from W Section Line

Lease Name: PAULY 3002

Well #: 6-1H

County: SUMNER

Total Vertical Depth: 3540 feet

Operator License No.: 35053

Op Name: TAPSTONE ENERGY, LLC

Address: PO BOX 1608

OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	18	60		30 sx cement
I1	7	4122		990 sx cement
L1	4.5	8358		360 sx cement
PROD	7	4122		990 SX
SURF	9.625	181		147 SX
SURF	9.625	191		147 SX
T1	2.875	3053		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/17/2015 12:00 PM

Plug Co. License No.: 35086

Plug Co. Name: SJL WELL SERVICE, LLC

Proposal Rcvd. from: BOONE DAVIDSON

Company:

Phone: (620) 840-2367

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: PARTIAL

Date/Time Plugging Completed: 09/17/2015 4:00 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

PREVIOUS OPERATOR SET CIBP @ 3396' WITH CEMENT TOP ON TOP, RAN TUBING INTO VERIFY TAGGED TOC @ 3181'. LOADED HOLE WITH MUD. THE 7 INCH CASING HAD CEMENT CIRCUALTED FROM BOTTOM TO SURFACE. RAN TUBING INTO 500' SPOTTED 50 SX CEMENT, PULLED TUBING TO 250' CIRCUALTED TO SURFACE WITH 70 SX CEMENT. CUT HEAD OFF TO VERIFY CEMENT AROUND 7", TOPPED OFF AND CLOSED, ON 9/18/2015.

Perfs:

Top	Bot	Thru	Comments
7976	8197	CSG	
7611	7905	CSG	
7108	7410	CSG	
6733	7035	CSG	
6358	6660	CSG	
4518	4800	CSG	
4240	8270	CSG	
4238	4450	CSG	

Remarks: HURRICANE SERVICES INC OUT OF GARNETT KS. PROVIDED CLASS A CEMENT FOR JOB. DENIED TA.
TMD= 8368

Plugged through: TBG

District: 02

Signed

[Signature]
[Signature]

(TECHNICIAN)

KCC WICHITA

SEP 28 2015 OCT 09 2015
RECEIVED *cm*