

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23842-00-00
Spot: N2SENWNW Sec/Twnshp/Rge: 32-31S-11W
940 feet from N Section Line, 990 feet from W Section Line
Lease Name: WHELAN Well #: 1-32
County: BARBER Total Vertical Depth: 4800 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4305		WITH 2 SX CMT
CIBP		4550		
PROD	5.5	4797	3050	WITH 120 SX CMT
SURF	8.625	225		WITH 190 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/16/2015 8:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: DEON HOWARD Company: VAL ENERGY Phone: (316) 263-6688

Proposed Plugging Method: CIBP @ 4305' WITH 2 SX CMT. PLGUA T 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 09/16/2015 10:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4305' WITH 2 SX CMT. 1ST PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4408	4418		
4370	4384		
4356	4418		


Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

OCT 09 2015
CLM

District: 01

Signed



SA

(KCC) WICHITA

RECEIVED
SEP 24 2015
KCC DODGE CITY

SEP 28 2015
RECEIVED