

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-20812-00-01
Spot: SWNW Sec/Twnshp/Rge: 11-29S-13W
3475 feet from S Section Line, 4779 feet from E Section Line
Lease Name: SWISHER UNIT-KESSLER #1 Well #: 1
County: PRATT Total Vertical Depth: 4774 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4190		WITH 2 SX CMT
CIBP		4375		
CIBP		4490		
CIBP		4710		
PROD	5.5	4762	2130	WITH 170 SX CMT
SURF	8.625	487		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/16/2015 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 4190' WITH 2 SX CMT. PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: PARTIAL
Date/Time Plugging Completed: 09/17/2015 9:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4190' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 510' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. HOLE WENT ON VACUUM. SDON TO LET CMT SET. 9/17/15: RUN IN & TAG TOC @ 200'. LOADED HOLE & SPOT 20 SX CMT AT 40'. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4745	4734		
4631	4623		
4415	4402		
4402	4415		
4293	4289		
4289	4293		
4260	4253		
4253	4260		
4220	4214		
4214	4220		

KCC WICHITA
OCT 02 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

OCT 09 2015

District: 01

RECEIVED
SEP 24 2015
KCC DODGE CITY

Signed Stephen J. Pfeifer
(TECHNICIAN)