

To: 1080428
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,202-0000

NW NE NE, SEC. 18, 'T' 25 S, R. 13 W 2 E

4950 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9263

Lease Name Curtis Well # 2

Operator: Champion Petroleum, Inc.

County Stafford 141.51

Name & Address P. O. Box 637

Well Total Depth 4354 feet

Ellinwood, KS 67526

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 291

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 8 Month: October Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2941

were: 5 1/2" at 4326' Perfs at 3710-16', 3762-66', 3821-26', 3852-54', 3895-00'

1st plug pump 1 sack hulls, 25 sx cement, 27 sx gel and 100 sx cement down 5 1/2"

2nd plug pump 100 sx cement down 8 5/8"

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:10 pm Day: 8 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls, 25 sx cement, 27 sx gel, and 85 sx cement down 5 1/2" Maximum pressure 500 psi and shut in 400 psi

2nd plug pumped 90 sx cement down 8 5/8" Maximum pressure 450 psi and shut in 250 psi

Remarks: No Recovery. Used 60/40 Pozmix 6% gel by BJ-Titan
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

STATE CORPORATION COMMISSION

DATE OCT 29 1985

Signed _____

OCT 28 1985

(TECHNICIAN)

INV. NO. 10747

CONSERVATION DIVISION

10-28-85

FORM CP-2/3
Rev. 01-84