

1 030296

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,087-0000

NW NW SE , SEC. 18 , T 25 S, R 13 W ~~XX~~

2310 feet N SE Corner of ~~WXX~~ section line

2310 feet W SE Corner of ~~WXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6393

Lease Name Brehm-Burk Well # 2

Operator: Brougner Oil, Inc.

County Stafford

Name & Address P. O. Drawer 1367

Well Total Depth 4325 140.56 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 382

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Mohawk Drilling, Inc. License Number 6394

Address 2401 Fourth National Bank Building, Tulsa, OK 74119

Company to plug at: Hour: 11:00 am Day: 3 Month: October Year: 19 84

Plugging proposal received from Wilbur Cotton

(company name) Mohawk (phone) 918-582-9992

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 840' with 50 sx cement

2nd plug at 420' with 40 sx cement

3rd plug hulls' - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plug water well with 5 sx cement Plugging Proposal Received by Steve Demont
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2:00 pm Day: 3 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 840' with 50 sx cement, 2nd plug at 420' with 40 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate

mouse hole with 10 sx cement, and plugged water well with 5 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton No. 918217
(If additional description is necessary, use BACK of this form.)

(If you observe this plugging.)

INVOICED

DATE 10-15-84

INV. NO. 4303

Signed Steve Demont
(TECHNICIAN)

10-3 NOV 7 1984