

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued May 26, 1967.

Operator's Full Name Chief Drilling Company

Complete Address: Box 797, Great Bend, Kansas 67530

Lease Name Curtis Well No. # 1

Location NW NE SE Sec. 20 Twp. 25 Rge. 13 (E) (W)

County Stafford Total Depth 4343'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:00PM Day 5th Month June Year 1967

The Above well was plugged as follows:

272' of 8 5/8" surface pipe, cemented with 255 sacks. 4335' of 5 1/2" long
string, cemented with 100 sacks. Top perferation 4274'. Bottom of the hole
was sanded to 4250', and cemented with 5 sacks, through the dump bailer.
2118' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed
in fluid to 270', Bridge plug and rock bridge from 270' to 260'. 4 sacks of
cement was mixed in a barrel, and put on plug at 260', through the dump bailer
and let set over week-end. Hole was bailed dry, and 21 sacks of cement was
added to the plug. Hole was filled with mud to 40', rock bridge from 40' to
30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/7/67

INV. NO. 5346-W

Signed: Archie Ebling
Well Plugging Supervisor