

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-185-21,476-0000 ✓

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Petromark Exploration, Inc.

Complete Address Copper Oaks Office Bldg., 7030 South Yale, Tulsa, Okla. 74127

Lease Name Lyon Well No. 1

Location SE NW NW Sec. 17 Twp. 25 Rge. 13 (~~EAST~~) (West)

County Stafford Total Depth 4326'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Mustang Drilling and Exploration and Sun Oil Well Cementing

Address P.O. Drawer 1609, Great Bend, Kansas License No. _____

Operation Completed: Hour: 6:00 PM Day: 6 Month: March Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: Anhydrite Top 827'
Hole circulated and Filled with mud. 60 sacks cement pumped
through drill pipe at 600'. 40 sacks cement pumped through
drill pipe at 400'. Hole Filled with mud to 40'. Plug and 1/2
sack hulls pushed to 40' and hole cemented to base of
cellar with 10 sacks cement. Rathole cemented with 10 sacks
cement.

Cement used: 50/50 Pozmix w/2% gel and 3% c.c.

Amount of Surface Casing: 8 5/8" - 408' set @ 415' - 325 sacks Common 3% c.c. 2% gel

I hereby certify that the above plugging instructions were given as herein stated.

Signed: _____
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Had well to plug in my own area.
Notified Answering Service.

RECEIVED
STATE CORPORATION COMMISSION

Signed: [Signature]
Conservation Division Agent

INVOICED

MAR 10 1982

DATE 3-12-82
INV. NO. 9633-W
CONSERVATION DIVISION
Wichita, Kansas

3-10-82