

*RP*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 16 1963  
10-16-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Rock Island Oil & Refining Co., Inc.

Complete Address: 321 W. Douglas, Wichita, Kansas

Lease Name Garner Well No. # 1

Location SW SW SE Sec. 17 Twp. 25 Rge. 13 (E) (W) W

County Stafford Total Depth 4385

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Woodman-Iannitti Drilling Co.

Address: 714 Union National Bldg., Wichita, Kan. License No. \_\_\_\_\_

Operation Completed: Hour 10:00 PM Day 11th Month December Year 1963

The Above well was plugged as follows:

370' of 10 3/4" surface pipe, cemented with 275 sacks. Fluid level  
was up in hole. 1st cementing plug and 1/2 sack hulls was pushed to 290',  
cemented with 30 sacks, through the drill pipe. Hole was filled with  
drilling mud to 40', 2nd cementing plug, bridged with hulls, cemented  
with 15 sacks to base cellar. Rat hole bridged and cemented with 2  
sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 12/19/63  
INV. NO. 8294-u