

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Raymond Oil Company

Complete Address: 410 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Walter Well No. # 1

Location SW SE SW Sec. 36 Twp. 25 Rge. 13 (E) (W) W

County Stafford Total Depth 4345'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Bert Self Casing Pulling Company

Address: Route 4, Hutchinson, Kansas License No. 48

Operation Completed: Hour 12:30 PM Day 27th Month April Year 1966

The Above well was plugged as follows:

245' of 8 5/8" surface pipe, cemented with 175 sacks. 4345' of 5 1/2" long string, cemented with 200 sacks. Top perforation 3600'. Bottom of the hole was sanded to 3590', and cemented with 5 sacks, through the dump bailer. 2400' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 235', rock bridge from 235' to 225'. 4 sacks of cement was mixed in a barrel, and put on plug at 225', through the dump bailer, and let set over-night. Next day hole was bailed dry, and hole was filled with 3 yards of ready-mix cement, from 213' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/28/66

INV. NO. 3123-W