

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 5 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Walter Well No. # 2

Location NE SW SW Sec. 36 Twp. 25 Rge. 13 (E) W

County Stafford Total Depth 4345'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Bert Self Casing Pulling Company

Address: Route 4, Hutchinson, Kansas License No. 48

Operation Completed: Hour 3:30PM Day 4th Month May Year 1966

The Above well was plugged as follows:

270' of 8 5/8" surface pipe, cemented with 200 sacks. 4305' of 5 1/2" long string, cemented with 200 sacks. This is an open hole. Bottom of the hole was sanded to 4300', and cemented with 5 sacks, through the dump bailer.

2835' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 265', rock bridge from 265' to 255'. 4 sacks of cement was mixed in a barrel, and put on plug at 255', through the dump bailer, and let set over-night. Next day hole was bailed dry, and 25 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/5/66
INV. NO. 3765-W