

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

DEC 29 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Bovaird Supply Company

Complete Address: Box 897, Great Bend, Kansas

Lease Name McCandless Well No. # A-1

Location NE NE SW Sec. 29 Twp. 25 Rge. 13 (E) (W) W

County Stafford Total Depth 4346'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Apex Casing Pulling Co., Inc.

Address: 739 E. Second St., Hoisington, Kansas License No. 544

Operation Completed: Hour 12:30PM Day 28th Month Dec. Year 1964

The Above well was plugged as follows:

. 320' of 8 5/8" surface pipe, cemented with 300 sacks. 4335' of 5 1/2" long  
string, cemented with 150 sacks. Bottom of the hole was sanded to 4265',  
and cemented with 5 sacks. Fluid level was up in the hole. Plug was push-  
ed to 300', and 10' of rock bridge. 25 sacks of cement was mixed in a  
barrel, and put on bridge plug at 290', through the dump bailer. This  
cement was left to set up. Hole was bailed dry. And hole was filled with  
mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the  
base of the cellar. 2819' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 12/29/64

INV. NO. 418-W