

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 145-8

LOCATION CNE-NW-SW

SEC. 19 TWP. 15 RGE. 13W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease J. C. McCandless

Operator Midstates Oil Corp Address Box #151 - Hays, Kans

Field _____ County Stafford

Total Depth 4378 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 1180 ft - Circulated with cement.
7" casing set at 4284 ft. Plugged back to 3450 ft
with cement - 100 sacks - Shot off & pulled the 7" casing
Well showing salt water from 1275 ft - Pumped in
Plug & 100 sacks of cement - Fill hole from 1275 ft to
150 ft with cement - Mud to 20 ft - Plug &
5 sacks of cement at the surface -
Pipe Pulling Co. Plugging Contractors

Conservation Div.
JUN 10 1950

6-10-50

STATE CORPORATION COMMISSION
C. W. [Signature]
District Conservation Agent

PLUGGING
FILE SEC 29 T 25 R 13W
BOOK PAGE 145 LINE 8

Date 6-5-50