

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

Stafford County, Sec. 36 Twp. 25S Rge. (E) 13(W)

Location as "NE/CNW/SW" or footage from lines SW NW SE/4

Lease Owner, Clay H. Newell

Lease Name Copenhagen Well No. 1

Office Address Stafford, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Aug. 30, 1954

Application for plugging filed " " 19 " "

Application for plugging approved " " 19 " "


Plugging commenced " " 19 " "

Plugging completed " " 19 " "

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Elves

Producing formation Depth to top Bottom Total Depth of Well 4252 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	289'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud to 285 ft.
set plug and run 20 sacks cement through drill
pipe. Mudded hole to 35 ft. set plug and run
10 sacks cement at the surface.

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1954
WICHITA, KANSAS

Name of Plugging Contractor Armer, Inc.
Address 710 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgewick, ss. I. C. Soonenberg (employee of contractor)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of September, 1954.

My commission expires February 13, 1956.

[Signature] Notary Public.

PLUGGING
FILED SEC. 267 25 R. 134
DSCX PAGE 60 LINE 44

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Clay H. Howell**

SEC. **36** T. **25S** R. **13W**
 LOC. **SW NW SE**

FARM **Copenhaver** NO. **1**

TOTAL DEPTH **4252'**

COUNTY **Stafford**
 KANSAS


COMM. **8/16/54**

COMP. **8/31/54**

SHOT OR TREATED

CONTRACTOR **Armer, Inc.**

ISSUED



CASING

20	10	
15	8	289'
12	6	
13	5	

ELEVATION **1904 K.B.**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & Clay	175
Red Bed	289
Red Bed & Shale	875
Red Bed, Shale & Shells	1365
Shale & Shells	1630
Shale & Lime	2910
Lime - Broken	3045
Lime	3225
Shale & Lime	3555
Sand & Shale	3630
Lime	3965
Shale & Lime	4015
Cherty Lime	4050
Lime & Chert	4090
Chert	4111
Chert Lime, Shale & Sand	4128
Lime & Chert	4149
Chert	4214
Lime & Chert	4245
Shale & Sand	4252

FORMATION TOPS: (R.B. Meas.)

HEBEN R	3485
TORONTO	3504
DOUGLAS	3523
ERONH LINE	3650
LANSING	3668
BASE K.C.	3969
MISSISSIPPI	4076
VIOLA	4155
SIMPSON	4235

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER, INC.

STATE OF KANSAS
 COUNTY OF SEDGWICK

NOTARIAL COMMISSION
 EXPIRES FEBRUARY 13, 1956
 BY *[Signature]*
 NOTARY PUBLIC

Subscribed and sworn to before me, a notary public, in and for said County and State this 2nd day of September, 1954.

PLUGGING
 FILE SEC 36 T 25 R 13W
 BOOK PAGE 60 LINE 44

[Signature]
 Notary Public

My Commission expires February 13, 1956.