

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County, Sec. 36 Twp. 25 Rge. (E) 13 (W)

Location as "NE/CNW%SW%" or footage from lines SW SE NE/4

Lease Owner M. B. Armer

Lease Name Helmke Well No. 1

Office Address 710 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed Jan. 2, 19 54

Application for plugging filed Jan. 8, 19 54

Application for plugging approved Jan. 8, 19 54


Plugging commenced Jan. 8, 19 54

Plugging completed Jan. 13, 19 54

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4306 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	261	None
				5 1/2"	4160	3541

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Drilled out cement to 4133 1/2 ft. Perforated 4100 ft. to 4110 ft.

Filled with sand to 4090 ft. and ran 5 sacks cement with dump

bailes. Pulled 5 1/2" casing and pumped hole full of mud, set

plug and squeezed with 90 sacks cement through plug head on

8 5/8". Cement from 260 ft. to 4 ft., mud plug - cement pumped

by Halliburton Oilwell Cementing Co.

JAN 20 1954
1-20-54
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R - S Pipe Pulling Company

Address Ellinwood, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss. L. C. Sponenberg (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 19 54

Rose Lurvey Notary Public.

My commission expires February 13, 1956.

PLUGGING
FILE REC 36 T 25 R 134
BOOK PAGE 7 LINE 43

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **M. B. Armer**

SEC. 36 T. 25S R. 13W

FARM **Helmke**

NO. 1

LOC. SW SE NE

TOTAL DEPTH **4303'**

COUNTY **Stafford**


COMM. **12/9/53**

COMP. **12/29/53**

KANSAS

SHOT OR TREATED

CONTRACTOR **Armer, Inc.**



ISSUED

CASING

20	10	
15	8	261'
12	6	
13	5	4160'

ELEVATION **1896 K.B.**

PRODUCTION **D&A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	165
Sand & Red Bed	261
Red Bed, Shale & Shells	525
Shale & Red Bed	745
Anhydrite	765
Red Bed, Salt & Shells	950
Shale, Shells & Salt	1365
Shale & Shells	1660
Shale & Lime	1855
Sandy Lime & Shale	1985
Lime & Shale	2465
Shale	2810
Shale & Shells	2885
Lime	3045
Lime & Shale	2175
Lime	3480
Lime Sandy Shale	3575
Shale & Shells	3658
Lime	4060
Chert Lime	4095
Chert & Sand	4111
Chert & Lime	4140
Cherty Lime	4175
Lime & Chert	4216
Shale & Sand	4247
Lime & Shale	4303

FORMATION TOPS (R.B. Meas.)

MISSISSIPPI	4061
VIOLA	4123
KINDERHOOD SAND	4089
SIMPSON SHALE	4200
SIMPSON SAND	4212
ARBUCKLE	4268

RECEIVED
 STATE COMMISSION
 JAN 2 1954

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER, INC.

By *P. P. Armer*

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a notary public, in and for said County and State this 5th day of January, 1954.

Core Lacey
 Notary Public

My Commission expires February 13, 1956.

PLUGGING
 FILE SEC 36 T 25 R 13W
 BOOK PAGE 7 LINE 43