


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 29 Twp. 25 Rge. 13W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW/4  
Lease Owner Bovaird Supply  
Lease Name Mc/Candless Well No. #1  
Office Address Box 897 Great Bend Kans.  
Character of Well (completed as Oil, Gas or Dry Hole) OIL  
Date well completed 10/20 1958  
Application for plugging filed Yes 11/16 1964  
Application for plugging approved Yes 11/18 1964  
Plugging commenced 12/10 1964  
Plugging completed 12/28 1964  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 10/30 1964  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4350 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2819

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
4350  
Sanded back 5-1/2 from 4330 to 4306 mixed and dumped  
5sx cement on sand bridge.  
set plug in 8-5/8 at 300 ft. With ten foot rock bridge mixed and dumped  
25 sx cement on bridge mudded hole to 40 ft. mixed and dumped 10 sx.  
cement on ten foot rock bridge.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 8 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Apex casing pulling co  
Address 739 East 2ND Hoisington Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.  
Ben Thompson (owner) (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben Thompson  
739 East 2nd Hoisington  
(Address)

SUBSCRIBED AND SWORN TO before me this 7<sup>th</sup> day of January, 1964

My commission expires 1/6-20-67

Notary Public.

ROTARY DRILLING LOG

OPERATOR: McKnab Production Company  
 E. M. McCandles "A" No. 1  
 NE NE SW Sec. 29-25-13W,  
 Stafford County, Kansas

CONTRACTOR: Capitt Drilling, Inc.  
 COM: 10/1/58  
 COMP: 10/20/58

Remarks: Set 320' of 8-5/8" surface casing cemented with 300 sacks cement.

Formations:

Surface Clay	40'
Sand & Red Bed	303'
Shale	320'
Red Bed & Shale	940'
Shale & Red Bed	970'
Shale & Shells	1735'
Shale	1953'
Lime & Shale	2080'
Lime	2195'
Lime & Shale	2304'
Lime	2413'
Lime & Shale	3610'
Shale & Lime	3718'
Lime	3822'
Lime & Shale	3850'
Lime	4020'
Lime & Shale	4072'
Lime	4125'
Cherty Lime	4186'
Lime & Shale	4238'
Lime & Chert	4270'
Lime	4282'
Lime - chert	4293'
Sand	4310'
Sand & Shale	4333'
Shale & Lime	4350'
Rotary Total Depth	4350'

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 8 1965

CONSERVATION DIVISION  
 Wichita, Kansas

Set 5-1/2" casing at 4345.50' cemented with 150 sacks cement.

We certify the above log is true and correct to the best of our knowledge and belief.

CAPITT DRILLING, INC.

*R.R. McNicol*

R. R. McNicol