

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-11059-0000

LEASE NAME Leiss #4

WELL NUMBER _____

SPOT LOCATION C W/2 NE NW

SEC. 29 TWP. 25s RGE. 13w(E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 1/10/85

Plugging Completed 1/16/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR K & E Drilling, Inc.

ADDRESS 100 S. Main, Suite 300, Wichita, Ks. 67202

PHONE #(316) 264-4301 OPERATORS LICENSE NO. 5266

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4373'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	328'	none
				5 1/2"	4354'	3107'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 3750' & 5 sacks cement. Shot pipe at 3518', 3320', 3100'.

Pulled 99 joints of pipe. Plugged well with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug, & 125 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling

License No. 6050

Address Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

JAN 22 1985

R. Darrell Kelso (employee of operator) of Conservation Division
(operator) of above-described well, being first duly sworn on oath, says: That Wichita, Kansas
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 18th day of January, 1985

My Commission expires:



Notary Public

ROTARY DRILLING LOG

OPERATOR: Sam P. Wallingford, Inc.
LEISS NO. 4
C/W/2 NE NW Sec. 29-25-13W,
Stafford County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
COMM: 11/1/60
COMP: 11/16/60

Remarks: Set 332' of 8-5/8" surface casing set at 328' cemented with 225 sacks HA-5 Pozmix w/1/4# flocele.

Formations:

Surface hole	328'
Red Bed & Shale	510'
Shale & Shells	1470'
Shale & Lime	1918'
Lime & Shale	2190'
Shale & Lime	2415'
Lime	2458'
Lime & Shale	2640'
Shale & Lime	3075'
Lime & Shale	3205'
Lime (Chalky)	3321'
Lime & Shale	3390'
Lime	3560'
Lime & Shale	3715'
Lime	4196'
Lime & Chert	4247'
Lime	4285'
Sand	4290'
Lime	4373'
Rotary Total Depth	4373'

Set 5-1/2" Casing at 4349' G.L.M.
(4354 R.B.M.) cemented with 175
sacks common cement.

We certify the above log is true
and correct to the best of our
knowledge and belief.

CAPITT DRILLING, INC.

R. R. McNicol

R. R. McNicol

RECEIVED
STATE CORPORA. OR COMMISS.
OCT 25 1964
CONSERVATION DIVISION
Wichita, Kansas