

15-185-11053-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117.

API NUMBER _____

LEASE NAME Leiss #3

WELL NUMBER _____

SPOT LOCATION C E/2 SE NW

SEC. 29 TWP 25s RGE 13w (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 12/21/84

Plugging Completed 1/16/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR K & E Drilling, Inc.

ADDRESS 100 S. Main, Suite 300, Wichita, Ks. 67202

PHONE # (316) 264-4301 OPERATORS LICENSE NO. 5266

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4366'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	300'	none
				5 1/2"	4364'	3038'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4200' & 5 sacks cement. Shot pipe at 3532', 3233', & 3038'. Pulled 94 joints of pipe. Plugged well with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug, & 125 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

RECEIVED

STATE OF Kansas COUNTY OF Rice STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) Jan 22 1985
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 18th day of January, 19 85

My Commission expires: _____



Irene Hoover
Notary Public

DRILLER'S LOG

COMPANY: McKNAB PRODUCTION CO., INC.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: LEISS #3
 LOCATION: E $\frac{1}{2}$ SE $\frac{1}{4}$ NW $\frac{1}{4}$ SEC. 29-25S-13W
 STAFFORD COUNTY, KANSAS
 COMMENCED: FEBRUARY 16, 1959
 COMPLETED: MARCH 2, 1959

0	180	Sand, Shale		
180	300	Shale & Redbed	<u>TOPS:</u>	
300	560	Redbed	Anhydrite	847
560	847	Redbed & Shells	Heebner	3542
847	865	Anhydrite	Toronto	3562
865	1175	Redbed, Shale & Shells	Douglas	3582
1175	1525	Shale	Br. Lime	3698
1525	1860	Shale & Shells	Lansing	3722
1860	2695	Lime & Shale	Base K.C.	3992
2695	3785	Shale & Lime	Marmaton	4040
3785	4365	Lime	Mississippi	4108
	<u>4365</u>	<u>Rotary Total Depth</u>	Kinderhook	4166
			Simpson	4274
			Elevation	1961 K

Set 8 5/8" surface casing @ 300' with 250 sacks 50-50 posmix HA 5 Cement
 Set 5 1/2" casing @ 4364' with 150 sacks common cement.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Leiss #3, located E $\frac{1}{2}$ SE $\frac{1}{4}$ NW $\frac{1}{4}$ of Section 29, Township 25 South, Range 13 West, Stafford County, Kansas, as reflected by the files of Leben Drilling, Inc. STATE CORPORATION COMMISSION

OCT 25 1984
 LEBEN DRILLING, INC. CONSERVATION DIVISION
 Wichita, Kansas

Frank Hamlin
 Frank Hamlin

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS:

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 7th day of March, 1959

Ruth N. Benjamin
 Ruth N. Benjamin, Notary Public

My commission expires:
 June 17, 1961