


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County, Sec. 29 -Twp. 25S Rge. 13 (X) (W)

Location as "NE/CNW/SW" or footage from lines SW SE NE
Lease Owner McKnab Production Company
Lease Name Curtis Well No. 1
Office Address 1700 Broadway Denver, Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 17 1960
Application for plugging filed 9-17-60 19
Application for plugging approved 9-17-60 19
Plugging commenced 9-17-60 19
Plugging completed 9-17-60 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4393 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	307'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 305' w/25 sx. cement
Top plug @ 40' w/10 sx. cement & 1/4 sx. hulls
Plug down @ 9:30 P.M. (9-17-60)

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Bldg. Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg. Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 1960
Bette J. Behymer
Bette J. Behymer Notary Public.
My commission expires July 27, 1964

DRILLER'S LOG


COMPANY:	MC KNAB PRODUCTION COMPANY, INC.
CONTRACTOR:	LEBEN DRILLING, INC.
FARM:	CURTIS #1
LOCATION:	SW SE NE Sec. 29-25S-13W STAFFORD COUNTY, KANSAS
COMMENCED:	9-2-60
COMPLETED:	9-17-60

0	110	Clay & Sand
110	307	Shale, Sand & Blue Shale
307	840	Shale & Redbed
840	875	Anhydrite
875	950	Redbed & Shale
950	1390	Shale & Shells
1390	1940	Shale & Lime
1940	2215	Shale & Lime
2215	2430	Shale & Lime
2430	2625	Lime
2625	2710	Lime w/ Sand Streaks
2710	3045	Lime & Shale
3045	3158	Lime & Shale
3158	3365	Lime
3365	3530	Lime
3530	3710	Lime
3710	3795	Lime
3795	3835	Lime & Chert
3835	3880	Cherty Lime
3880	3995	Lime
3995	4035	Lime & Shale
4035	4165	Lime
4165	4225	Cherty Lime
4225	4285	Chert & Lime
4285	4355	Lime
4355	4360	Lime
4360	4393	Arbuckle
	<u>4393</u>	<u>Rotary Total Depth - D & A</u>

RECEIVED
 STATE GEOLOGICAL COMMISSION
 SEP 20 1960
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" surface casing @ 307' with 125 sacks HA5 cement.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Curtis #1, located SW SE NE of Section 29, Township 25 South, Range 13 West, Stafford County, Kansas, as reflected by the files of Leben Drilling, Inc.


 Frank Hamlin

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 22nd day of September, 1960.


 Bette J. Behymer, Notary Public

My Commission Expires:
 July 27, 1964