

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

STAFFORD

County. Sec. 29 Twp. 25S Rge. 13W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE4

Lease Owner AMERICAN PETROLEUM COMPANY

Lease Name LEISS Well No. 1

Office Address

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-26-60 19

Application for plugging filed 4-26-60 19

Application for plugging approved 4-26-60 19

Plugging commenced 4-26-60 19

Plugging completed 4-26-60 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Broadfoot, St. John, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand, Shale & Red Bed	Surface Casing	-0-	310'	8-5/8"	310'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGED: Filled hole with mud 4371' up to 300'. Set bridge using 1/3 sk. hulls, wood plug, 20 sx. cement through drill pipe. Filled hole with mud up to 35'. Set bridge using 1/2 sk. hulls, wood plug, 10 sx. cement to cellar Zero.

Job Completed: 4-26-60 - 5 a.m.

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
Address 208 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. HONAKER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker C. T. HONAKER, DRLG. SUPT.
BOX 232, RUSSELL, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of APRIL, 1960

Notary Public

My commission expires 10-17-63



LEISS #1 - SE4, Sec. 29-25S-13W - Stafford County, Kansas

AMERICAN PETROIEUM CO. - Operator
SIERRA PETROIEUM CO., INC. Contractor

Elevation: 1946' K.B.
T. D. : 4371'

Commenced Drilling: 4-12-60
Completed Drilling: 4-25-60

CASING:

Set 8-5/8" at 310'

CEMENT:

with 275 Sacks

FORMATION:

Sand
Shale & Red Bed
Red Bed
Anhydrite
Shale & Shells
Shale & Lime
Lime
Lime & Shale
Lime
Lime & Shale
Lime
Viola

DEPTH:

190'
310'
830'
865'
1735'
3424'
3595'
3730'
4070'
4125'
4227'
4371'

TOPS:

Anhydrite
Heebner
Toronto
Douglas
Brown Lime
Lans. L.C.
Mississippi
Kinderhook
Viola
Simpson

830'
3567'
3584'
3610'
3725'
3749'
4165'
4180'
4206'
4365'

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1960
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF RUSSELL) ss:

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Honaker

Subscribed and sworn to before me this 27th day of April 1960.

Gerry Smith
Notary Public

My commission expires: 10-17-63

