

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 29 Twp. 25S Rge. (E) 13 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines E/2 SW SW

Lease Owner Beardmore Drilling Company

Lease Name McCandless Well No. 3

Office Address 603 Petroleum Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed January 6 19 52

Application for plugging filed January 6 19 52

Application for plugging approved January 6 19 52


Plugging commenced January 6 19 52

Plugging completed January 6 19 52

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough, Box 207, Great Bend, Kansas

Producing formation Depth to top Bottom Total Depth of Well 388.3 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	111.5	8-5/8	111.5	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

Mud from 388.3 to 250, plug at 250, 15 sacks cement, mud to 35, 10 sacks cement to complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Company

Address 603 Petroleum Bldg., Wichita, 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, Heber Beardmore, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore

603 Petroleum Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of January, 19 52.

Annette R. Kennalley Notary Public.

My commission expires January 19, 1955

PLUGGING
FILE SEC-29-T-25R-32
BOOK PAGE 126 LINE 33

McCandless #3

E/2 SW SW
Section 29-25S-13W
Stafford County, Kansas

Drilled for: Beardmore & Simon Lebow
Drilled By: Beardmore Drilling Company

Casing Record:

8-5/8" 1145' w/450 Sacks

Drilling Commenced: December 27, 1951
Drilling Completed: January 6, 1952

Elevation; DF 1957
GR 1955

<u>FORMATION</u>	<u>DEPTHS</u>
Sand Soil	30
Sand	210
Red Rock - Shale	335
Red Rock - Sandy Shale	550
Shale - Shells	800
Lime - Shale	865
Shale - Lime	1100
Shale - Shells	1675
Lime Broken	2405
Shale - Lime	3365
Lime - Shale	3450
Lime Broken	3640
Lime - Shale	3795
Lime - Cherty	3834
Lime	3883 T. D.

D & A

TOPS:

Brown Lime	3711
Lansing	3734

DST #1 - 3820-40 - Weak blow for 45 minutes, shut in 15 minutes, recovered 65'
Muddy water, BHP 1110#

DST# 2 - 3872-3883 - Good blow at opening with blow decreasing to weak blow at
end of 1 hour. Shut in 15 minutes, recovered 30' mud
BHP 75#

STATE OF KANSAS
ss
COUNTY OF SEDGWICK

JAN 10 1952

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above-described, to the best of my knowledge and belief.

Al. Beardmore

Subscribed and sworn to before me this 10th day of January 1952.

Annette A. Kennally
Notary Public

My Commission Expires: January 19, 1955

PLUGGING
FILE SEC 29-1-25 R. 13W
BOOK PAGE 13 LINE 33