

15-185-12448-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 11/11/58

LEASE NAME J.C. McCandles "B" #2

WELL NUMBER _____

SPOT LOCATION C W/2 NW NE

SEC. 30 TWP. 25 S. RGE. 13 W (E) or

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 3/27/84

Plugging Completed 4/3/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR K & E Drilling

ADDRESS 100 S. Main, Suite 300, Hardage Center, Wichita, Ks. 67202

PHONE # (316) 264-4301 OPERATORS LICENSE NO. # 5266

Character of Well _____
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4335'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASINO RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4 5"	312' 4331 1/2'	none 2941'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Sanded to 3800' & ran 5 sacks cement. Shot pipe at 3385', 3276', 3180', & 2941'.

Pulled 90 joints of 5 1/2" Pumped well with 1 hull. 15 gal. 50 cement, 15 gal. 1 hull, released plug & 150 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

APR 12 1984

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 10th day of April, 1984

 IRENE HOOVER
State of Kansas
My Comm. Exp. Aug. 15, 1985

Irene Hoover
Notary Public

My Commission expires _____

ROTARY DRILLING LOG

OPERATOR: McKnab Production Company
 J. C. McCandles No. 2
 C W/2 NW NE Sec. 30-25-13W,
 Stafford County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
 COMM: 10/22/58
 COMP: 11/11/58

Remarks: Set 10-3/4" surface casing
 at 312' cemented with 275
 sacks cement.

Formations:

Surface Clay	210'
Red Bed	380'
Red Bed & Shale	856'
Anhydrite	874'
Shale & Red Bed	955'
Red Bed	980'
Shale	1735'
Shale & Shells	1780'
Lime & Shale	1902'
Lime	2015'
Lime & Shale	2120'
Lime	2405'
Lime & Shale	2770'
Bro. Lime & Shale	2820'
Shale & Lime streaks	2900'
Shale w/Lime Streaks	3055'
Shale & Lime Streaks	3115'
Lime & Shale	3340'
Lime	3410'
Lime Shale	3519'
Lime & Shale	3569'
Lime	4250'
Lime & Chert	4263'
Lime (Cherty)	4280'
Lime	4299'
Sand & Shale	4305'
Lime & Shale	4335'
Rotary Total Depth	4335'

Set 5-1/2" casing at 4331-1/2'
 cemented with 325 sacks common
 cement.

We certify the above log is true
 and correct to the best of our
 knowledge and belief.

CAPITT DRILLING, INC.

R. R. McNicol
 R. R. McNicol

RECEIVED
 STATE CORPORATION COMMISSION

JAN 23 1984

CONSERVATION DIVISION
 Wichita, Kansas