


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit.
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 26 Twp. 25 Rge. 13 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
SE NW SE

Lease Owner Dudrey Oil
Lease Name Dudrey Well No. 1
Office Address 1900 Harrison Street Great Bend, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) DRY HOLE



Locate well correctly on above
Section Plot

Date Well completed June 3 1981
Application for plugging filed June 3 1981
Application for plugging approved June 3 1981
Plugging commenced 12:00 PM June 2 1981
Plugging completed 1:00 A.M. June 3 1981
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Morris Leslie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4315'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

35 sx. at 650'
30 sx. at 340'
10 sx. at 40'
10 sx. in rat hole

RECEIVED
STATE CORPORATION COMMISSION

JUN - 9 1981

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton CONSERVATION DIVISION
Wichita, Kansas


STATE OF Kansas COUNTY OF Barton, ss.
L. D. Davis (~~EMPLOYEE OF OWNER~~) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. D. Davis
L. D. Davis Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of June, 1981.

Bessie M. DeWerff
Bessie M. DeWerff Notary Public.

My commission expires 5-20-85



DRILLERS WELL LOG

L. D. DRILLING, INC - CONTRACTOR DUDREY OIL - OPERATOR

DUDREY # 1

T. D. 4315
ELEV. 1908 K.B.

COMMENCED: 5-26-81
COMPLETED: 6-3-81

CASING:

8 5/8" set at 341'

CEMENT:

W/300sx. 50/50 Pozmix, 2% Gel, 3% CC

FORMATION

Sand
Red Bed
Anhy.
Shale & Shells
Shale
Lime & Shale
Shale & Lime
Lime & Shale
R.T.D.

DEPTH

0 - 129
129 - 772
772 - 792
792 - 1125
1125 - 1500
1500 - 2075
2075 - 2425
2425 - 4315
4325

FORMATION TOPS

LOG

Heebner	3482	(-1574)
Toronto	3501	(-1593)
Brown Lime	3647	(-1739)
Lans. K/C	3673	(-1765)
Base K/C	3966	(-2058)
Conglomerate	4060	(-2152)
Mississippi	4090	(-2182)
Viola	4123	(-2215)
Simpson Shale	4206	(-2298)
Arbuckle	4287	(-2379)
Log T.D.	4311	(-2403)

AFFIDAVIT

STATE OF KANSAS)
COUNTY OF BARTON) ss

RECEIVED
STATE CORPORATION COMMISSION

I certify that this is a true and correct copy of the above log to the best of my knowledge. JUN - 9 1984

CONSERVATION DIVISION
Wichita, Kansas

L. D. DRILLING, INC.

L. D. Davis
L. D. Davis

Sworn to and subscribed before me this 5th day of June, 1981.
My appointment expires: 5-20-85

Bessie M. DeWerff
Bessie M. DeWerff, Notary Public.

